BRUHATH BANGALORE MAHANAGARA PALIKE,
Office of the Executive Engineer Dasarahalli Division,
Modified SCHEDULE-B

Name OF Work: Construction of SSM wall at Survey no 33 Mallasandra in Ward no 13 in Shettyhalli Sub Division.

SLNo	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	332.24	105.00	Rupees One Hundred Five Only
2	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 kgs, using 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregate @ 0.465cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	65.44	4691.00	Rupees Four Thousand Six Hundred Ninety One Only
3	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	610.84	4653.00	Rupees Four Thousand Six Hundred Fifty Three Only

Signature of Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

4	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	71.25	5588.00	Rupees Five Thousand Five Hundred Eighty Eight Only
5	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 2 Km	Cum	392.24	65.00	Rupees Sixty Five Only
	EIRL Items				
6	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and achoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Ton	4.67	56341.48	Rupees Fifty Six Thousand Three Hundread Forty One and Paise Forty Eight Only
7	Providing and removing centring, shuttering,propping etc., and removal of form work for vertical surface such as walls at any thickess, including attached pilastrers, buttresses, plinth and srring courses cost of all materials,labour complete as per specifications	Sqm	244.82	272.38	Rupees Two Hundred Seventy Two And Paise Thirty Eight Only

Signature of Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner